PLANTING NOTES

Designs Are The Property of The Michael Boice Collaboration. Un-authorized Use of Plans is Strictly Prohibited

1. All plant material must conform to American Standard for Nursery Stock ANSI Z60.1-2014

2. Voluntary Alternates/Plant substitutions must be approved by the Designer/Landscape Architect, Planning Board and or Zoning Administrator

3. All plant material delivered to the site and or planted must be maintained by the Landscape Contractor until the scope of agreed Landscape work is complete

4. All wire baskets must be either removed from the root ball or cut from the root ball after placing the plant in the planting hole

5. All burlap must be removed from root balls or cut away from the root ball after placing the plant in the planting hole. All planting holes must be 50% wider than the root ball or container root mass.

6a. The indigenous soil or back fill for major trees must not be conditioned unless rocky or unsuitable conditions are present

6b. Incorporate 50% organic soil media and slow release fertilizer per instructions into indigenous soil used to back fill shrubs, perennials and ground cover. Ground cover areas in particular may require mechanical tilling in an effort to create a friable soil texture

6c. Any soil glazing created by the back of the shovel shall be removed by reversing the shovel and caving in the planting hole

7. A soil pH test is highly recommended before planting begins

8. All existing unwanted plant material and weeds and their roots systems must be completely removed from planting beds prior to installing new plant material. The use of Round-Up may be required to eliminate invasive/stoloniferous weeds. Only a licensed professional may apply Round-Up

9. Only non-dyed natural mulch may be used. Install mulch to a depth of 2" - 3"

10. Stake any trees or plants that may be affected by high wind loads.

11. Where an automatic irrigation system is recommended, the Landscape Contractor shall provide proof of CID, CIC, CIT - Certified Irrigation Designer, Contractor, Technician through the Irrigation Association

12. It is the Landscape Contractor's responsibility to comply with all local and state codes. Any permits required for the Landscape Contractor's work must be obtained by the Landscape Contractor

13. It is the Landscape Contractor's responsibility to coordinate the planting schedule with the owner

14. Any deviations from the design due to unkown site conditions must be brought to the attention of the Designer/Landscape Architect

15. All Grasses and perennials must be cut back either in fall or early spring - before new foliage emerges. Pennisetum and Bouteloua must not be pruned lower than 12". Liriope must be cut back in late fall/early winter, not spring. The Liriope can be cut back using a small lawn mower set at its highest setting.

16. All plant material shall be maintained in a healthy condition for the life of the use of this project.

PLANTING LIST

GENUS SPECIE	COMMON NAME	SIZE	KEY	QUANTITY	NOTES	Zone
Tilia tomentosa	Silver Leaf Linden	3"-3.5" cal. branched 5-6'	TT - Labeled	11	Native, fragrant pollinator friendly	4-7
Hydrangea paniculata 'Little Quick Fire'	Little Quick Fire Hydrangea	5 gal	Labeled	11	White flowers in spring fade to red in fall	4-8
Hypericum frondosum 'Sunburst'	Sunburst St John's Wort	3 gal	Labeled	16	Yellow flowers summer native specie	5-8
Pycnanthemum muticum	Mountain Mint	2 al	Labeled	18	Native, pollinator, Drought tolerant	4-9
Pennisetum alopecuroides 'Red Head'	Red Headed Fountain Grass	2 gal	Labeled	56	Introduced Drought tolerant	5-9
Schizachyrium scoparium 'Standing Ovation'	Standing Ovation Little Bluestem	2 gal	Labeled	84	Native grass, intense blue color	3-10
Bouteloua gracilis 'Blonde Ambition'	Blonde Ambition Blue Gramma Grass	2 gal	Labeled	48	Native, quaking seed heads	3-10
Liriope spicata 'Variegata'	Variegated Liriope	1 gal	Labeled	1,100	Low Grassy texture, Purple Flowers	5-10

The Michael Boice Collaboration
DESIGNERS AND MAKERS OF FINE LANDSCAPES
845-702-1004
11 South Fowlerhouse Road Wappinger Falls, New York 12590

Date | September 22, 2021 Revisions |
mob September 27, 2021 circulators, green space, landscape
mob October 1, 2021 layout
mob December 20, 2021 layout changes
mob May 16, 2022
mob December 20, 2021 layout changes
mob June 14, 2022
more quantities, add dogwood
mob December 23, 2022
more grass count
mob January 24, 2023
more plant counts
mob February 21, 2023
notes per the town, scale
mob March 23, 2023
plant quantities

Scale | ...

Ready Coffee PLANT TABLE AND SPECIFICATIONS
Albant Post Road Hyde Park, New York